


miniPOCKET

Transferring platform



INSTALLATION INSTRUCTIONS



As far as the following items are concerned : general instructions, safety instructions, responsibility and warranty, material receiving and storage on site, packing, waste disposal, cleaning and maintenance, please consult the manual "**SAFETY AND MATERIAL HANDLING ON SITE**".









INDEX

0	MANUAL READING GUIDE	3
0.1	CHAPTER SYMBOLS	3
0.2	IMPORTANT ITEMS.....	3
0.3	INDIVIDUAL SAFETY DEVICES	3
1	PLATFORM LIFT: GENERAL FEATURES AND DESCRIPTION	4
2	TOOLS REQUIRED FOR INSTALLATION	5
3	BOX CONTENT.....	6
4	MATERIAL HANDLING ON SITE	6
5	PRELIMINARY ADVICE	7
6	PRELIMINARY OPERATIONS	8
6.1	INSTALLATION PLACE ARRANGEMENT	8
6.2	ELECTRICAL COMPONENTS : PREPARATION	8
6.3	CONSTRUCTION WORKS: CHECK PROCEDURES.....	9
7.1	PLATFORM ARRANGEMENT	10
7	PLATFORM INSTALLATION	10
7.2	HYDRAULIC PUMP UNIT AND CONTROLLER INSTALLATION (AND CABINET if expected)	11
7.3	SYSTEM PRESSURING	12
7.4	PLATFORM INSTALLATION	13
8	FIRST TEST SWITCH / CONTACTS CHECK	14
9	FINAL ELECTRICAL CONNECTION	14
9.1	CHECKING THE CONNECTION IN THE CONTROL BOARD AND INSULATION TEST	14
10	PLATES TO BE ATTACHED TO THE LIFT	15
11	FINAL TEST AND ADJUSTMENT.....	16
11.1	GENERAL STEPS	16
12	NOISE EMISSION.....	16
Appendix. 1	ANCHOR BOLTS usage instruction.....	17













1	General update	25.07.2016
Rev.	Descrizione	Data

0 MANUAL READING GUIDE










0.1 CHAPTER SYMBOLS

	General information		Positioning
	Box content		Installation
	Preliminary advice		Commissioning
	Read carefully		Electrical Wiring

0.2 IMPORTANT ITEMS

	General safety warning		Important notice		Read carefully
	Risk of electric shock		Risk of bodily injury (e.g. due to sharp angles or protruding parts)		Risk of damage to mechanical parts (e.g. during incorrect installation)
	Fire hazard		Hanging load		Risk of skin injury
	Risk of falling		No entry		Materials to be protected against bad weather conditions

0.3 INDIVIDUAL SAFETY DEVICES

	Hard hat		Ear protection		Safety harness and other accessories
	Overalls		Safety steel-toe boots with ankle protection		Safety glasses
	Dust masks		Work gloves Rubber gloves		First aid kit

The words **WARNING** and **CAUTION** are used to highlight the following risks of injury and damage:

WARNING	Serious danger to safety
CAUTION	Risk of damage to materials which may lead to safety risks




1 PLATFORM LIFT: GENERAL FEATURES AND DESCRIPTION

MiniPOCKET platform is a system focused in overcoming up to 780mm vertical rise even for short staircase because it supports maximum 800mm cross rise.


























Once closed, the platform remains hidden, solving environment impact problems possibly occurring in old town or of particular architectural value.

The system has perimetral fall arrest protections uncrushing and unscissor folder to offer users complete safety. In case of 500mm upper rise, according to laws, the system needs for protection bar on down side.

LIFTINGITALIA S.r.l. aims in promoting the constant improvement of its products and its technical features may be subjected to changes without any notice nor commitment.



FOR THE INSTALLATION OF THESE SYSTEMS BUILDING WORKS ARE NEEDED. THEY WILL BE REALIZED BY CUSTOMER, FOLLOWING STRAIGHTLY INSTRUCTIONS GIVEN DURING COMMISSION.


2 TOOLS REQUIRED FOR INSTALLATION						 	
Hammer				Tape measure			
Rubber hammer				Spirit level			
Flat-blade screwdriver				Spanner CH 5 ÷ 19 mm 2 each size			
Phillips screwdriver				Socket wrench CH 5 ÷ 19 mm			
				Ratcheting ring spanner S 5 ÷ 19 mm			
				Allen key with ball end CH 2 ÷ 8 mm			
Adjustable pliers				Portable lamp			
				Manual hoist, load ≥ 500 kg, length ≥ 2,5 m			
				Lifting belts, load ≥ 500 kg, length ≥ 2 m			
Drill				Screwdriver CH 5 ÷ 19 mm			
for Brickwork Metal		CH 5 ÷ 22 mm CH 2 ÷ 13 mm				Corner grinder	
							
Insulating tape				Chronometer			
				Digital multimeter			
				Transpallet			
				Bricklayer split			



3 BOX CONTENT



KIT F710.23.0001




10 x M4x30

KIT F710.23.0002



2 x M10x40

KIT F350.23.0027




4 x M10



4 x Ø10 - Ø30


LAYOUTS



4 MATERIAL HANDLING ON SITE



All materials may be portioned near lowest level. For materials transfer transpallets or stairlifts are suggested.





5 PRELIMINARY ADVICE




As far as the following items are concerned : general instructions, safety instructions, responsibility and warranty, material receiving and storage on site, packing, waste disposal, cleaning and maintenance, please consult the manual "**SAFETY AND MATERIAL HANDLING ON SITE**".



To support in introducing the subject, on this manual we mention "LIFT WELL/shaft (hoistway)" meaning it basis/bottom slab and vertical wall joining them.

- Important notes:
 1. Fix the tools to prevent an accidental fall;
 2. Strictly follow the steps described in this manual;
 3. Be careful when assembling single components, there may be sharp flaws (production leftovers);
- Before starting installation, it is necessary to remove all the residual materials and waste from the shaft.
- We recommend that you use only the nuts and bolts supplied with the lift.
- The bags containing nuts and bolts must be opened in accordance with the installation step indicated in this Manual.
- The instructions stated in this Manual, are valid for a concrete shaft, where wall plugs must be used. For brickwall shafts, consult the Appendix 1 to the this Manual. For steel shafts, the same procedure is applied, replacing plugs with normal screws.
- The stops are indicated with numbers 0, 1, 2, 3 both in this Manual and in the electrical scheme, where "0" stands for the lowest floor: the COP numeration could be different, according to the special needs of the user (example -1, 0, etc.).
- Least 2 people are required to make the assembly;
- Over 50Kg load needs moving pulley.






6 PRELIMINARY OPERATIONS




6.1 INSTALLATION PLACE ARRANGEMENT

To place the platform on its working place, you need to arrange a specific lifting coupler (at least 500 kg load) on vertical part of the lift shaft, fixing it to a rawplug on the ceiling or on an upstand frame (temporary scaffolding) doted by mechanic lifting fit for load lifting.



*UNBINDING
stock pictures*



*UNBINDING
stock pictures*

6.2 ELECTRICAL COMPONENTS : PREPARATION

miniPOCKET Platform supply is the result of platform switchboard connection to a common 230Vac, 50Hz, 10A socket.
We suggest to arrange a dedicated power line, directly connected to user main energy meter.

6.3 CONSTRUCTION WORKS: CHECK PROCEDURES

a. SHAFT: GENERAL CHECK PROCEDURES.

Lift shaft structure must be compliant to national laws about buildings subject in order to bear strenghts produced by lifting platform during its employment.

On project design biggest loads charging the shaft are specified.

The shaft must have the following features:

- Walls must be plastered in full height;
- Temperature range between +5 and +40°C;
- Opposite area free and accessible according to design instructions;
- Passages and canalization for electric and oleodynamic lines;
- Rainwater collection sump outside arrangement.

b. SHAFT VERTICAL DIMENSION: CHECK PROCEDURES.

The following dimensions must be checked:

- Travel
- Headroom
- Pit
- Small gate opening (when present on upper floor)
- Plumbing

The dimensions must be compliant with the project drawings (shaft section).

c. PLAN SHAFT DIMENSION: CHECK PROCEDURES.

The following dimensions must be checked:

- Width
- Depth
- Square
- Small gate position (when present on upper floor)

The dimensions must be compliant with the project drawings (shaft plan).




7 PLATFORM INSTALLATION



7.1 PLATFORM ARRANGEMENT


- Lay the platform near grave arranging it so that platform pipes exit point are near its dedicated corrugated;
- Pass the pipes/cable inside dedicated corrugated;
- Lift the platform using 4 fitted lifting eyebolts;




- Place the platform at the center of the grave near the spider;



Pull handily the pipes to drive them far from the bottom of the platform




- Remove the 4 lifting eyebolts;



7.2 HYDRAULIC PUMP UNIT AND CONTROLLER INSTALLATION (AND CABINET if expected)


- Arrange the hydraulic pump unit and the controller (or cabinet) where planned;

If cabinet, first arrange it, then verify where pipes/cables passage is, in order to open required and dedicated lift shafts.




To fix cabinet to wall through rawplugs.

KIT F710.23.0001



- Oleodynamic connections;
- Electrical connections according to electrical outline project;




7.3 SYSTEM PRESSURING



AT THIS STAGE PLATFORM ISN'T FIXED YET.
NO TRANSFER MOVEMENTS ALLOWED TO AVOID
UNBALANCING THE PLATFORM AND ANY DAMAGES
TO IT OR TO PEOPLE.



VERIFY THAT LIFTING EYEBOLTS
HAVE BEEN REMOVED.



- Verify on controller that all engine and device security connections are activated as reported on electric project outline and on terminal box top;
- Verify oleodynamics are activated as reported on electric project outline;
- Give potential difference to controller;
- With remote control (or floor switch when planned) make rise the platform;




DO ONLY VERTICAL MOVEMENT, the platform might
not shift.

- Put temporary some wood blocks near stripes;
- Lift the folding temporary arresting it to platform (the folding is not stopped to grave: its load pulls it towards ground);
- Put the maintenance KIT screws on grave;





Screws should not press on grave

- Verify with a tester that all contacts are properly working;
- Verify visually that there are no oil waste on circuit.



KIT F710.23.0002





7.4 PLATFORM INSTALLATION

- Verify the right positioning of platform using spider pointers.
Move platform base using lever;








Use the protection (wood board) between level and platform base.

- Drill on grave the arranged points;
- Fix platform base with supplied screws.



- Verify upper final limit contact;
The contact must be in perspective of the pivot positioned on pantograph roller.
When contact opens, platform has to stop.

- Lower the folding;
- With remote control (or floor switch when planned) put down the platform.





8 FIRST TEST SWITCH / CONTACTS CHECK



We suggest, before complete platform switch to:

- Check that on compartment there are no clear barriers or stick out materials interfering with platform movement;
- Verify that the STOP on column (if expected) is misfit;
- Verify that the 2 security screws on grave are mounted (maintenance kit);
- Verify that horizontal distance between platform and lobby level is less than 800mm;
- Verify folding to be stretched out and correctly positioned;
- Give potential difference to controller;
- Verify that activating transferring ultimate limit contact, the platform stops;
- Verify that, when the platform is on landing floor, the gap between the platform and the floor is less than 10 mm, otherwise please rehang the upper ultimate limit contact;
- Verify that, on slope stage, activating safety edge the platform stops, otherwise please regulate perimeter safety contracts;
- Verify that, driving the platform at lower floor, it regularly stops at the floor, otherwise, regulate lower ultimate limit contact;
- Verify that, electric cables positioned on machinery edge don't interfere to platform mechanisms;
- Make full travels.

Record the checked test as describe at point **2.2** of handbook "**Final Checks**".



9 FINAL ELECTRICAL CONNECTION



9.1 CHECKING THE CONNECTION IN THE CONTROL BOARD AND INSULATION TEST

Verify, according to electrical outline project, that all connection on controller have been made.

Make isolation test on circuits for earthing, a sit follows:

- Take platform out of floor to close security chain;
- Interrump the supply to motive power circuits;
- Disconnect controller circuits of earthing system and possible batteries;
- Connect a plug (generally the black one) to an external mass (for example motor casing, or the center of electric socket when earthing).
With the other plug please test all circuits (motive power, controller circuit, lights signals circuit, motor pump supply, alarm circuit);
- Detach the pulg (black) from external mass and connect it to clump of controller circuit and test it with all other circuits;
- Ripete the operation to test the precise isolation among all circuits.



10 PLATES TO BE ATTACHED TO THE LIFT



HYDRAULIC PUMP UNIT AND CONTROLLER INSTALLATION ON CABINET OF CONTROLLER

On cabinet top

**PLATFORM MACHINERY
DANGER**
ENTRANCE FORBIDDEN
WITHOUT AUTHORIZATION



**RECOMMENDED
HYDRAULIC OIL**
Mineral oil ISO VG 46
Viscosity ≥ 100
Working temperature: $+5^{\circ}\text{C}$ \div $+70^{\circ}\text{C}$

On main switch supply

PLATFORM MAIN SWITCH
CUT OFF THE POWER SUPPLY
ONLY WHEN THE PLATFORM
HAS REACHED THE FURTHER
DOWN FLOOR

**PLATFORM
DRIVING FORCE SWITCH**

LOAD SUPPORT

On column (if expected)



IN CASE OF EMERGENCY
PRESS TO STOP
TURN AS INDICATED
TO UNLOCK

On later stripes

**BEFORE ACCESS
GRAVE PUT SECURITY
SCREWS**
KIT F710.23.0002

PIT

On mechanics

ID NUMBER
/
ARIALIFT S.p.A. by LIFTINGITALIA S.p.A.
Via Castelli del Lavino, 10 - 43030 Reggiolo, Emilia (PR)

From external platform alarm

PLATFORM ALARM



To apply near call push button in
case of out of service system.



To apply near call push button
in case of public buildings.



11 FINAL TEST AND ADJUSTMENT



At this point continue on general system checks, in order to pledge ride comfort and execute later safety test according to laws (see point 2 of handbook "Final checks").



The operations as described in this paragraph are to be carried out by the qualified and authorized personnel.

11.1 GENERAL STEPS

Make sure the lift features match the contract details, the project drawings and the electrical scheme.

In particular:

- tension values in general and for each electrical device;
- duty load;
- speed;
- hydraulic unit features (load, tension, electric drive absorption, etc.);
- action of engine safety devices;
- platform micro-movement at floor;
- difference in height between empty car and full car when at stops;
- type and functioning of starting gate at upper floor;
- safety chain;
- safety distances;
- electrical insulation towards grounding, between operation circuit and driving force and between operation circuit and lighting.



12 NOISE EMISSION

Platform noises sources are unit and creeping of guides on shoes, in particular during rise and fall of full load.

Unit is always positioned inside fix column.


In different contexts analysed, the results were under 70dB(A).



Appendix. 1 ANCHOR BOLTS usage instruction

Appendix.1.1 CONCRETE SHAFT

Unless differently specified, all the anchor bolts are M10 and require holes to be arranged using the 10 mm drill bit, to the minimum 90 mm depth. The anchor bolt must be inserted in the hole up to 70 mm approximately.




Appendix.1.2 MASONRY SHAFT

The guide rail brackets assembly (shafts being constructed in either hollow or solid bricks), requires a certain gap reduction, to make up for the minor mechanical resistance of the walls.

The recommended gap is 750 mm, to be increased by 100 mm to avoid the guide rail junction, starting from the pit bottom ≤ 500 mm.

The number of bracket perimeters, with the standard values for pit (140÷200 mm), distance between floors (3000÷3200 mm) and headroom (2400÷2600 mm), is 4 for each stop.



SOLID BRICKS

The special kit F350.23.0026V01 for chemical bolts application is composed of:



- n° 16 zinc coated **THREADED BARS** M10x110, 45° cut (anti rotation);
- n° 2 300 ml vinyl ester **CARTRIDGES** (styrene free), suitable for elevated loads and application in humid holes, to be used with standard caulking guns;
- n° 2 multipurpose **MIXERS** Ø9 mm, additionally to the 4 mixers foreseen for the cartridges.

Each kit is sufficient for 8 brackets, required for approx. 1 stop.

For instance, 3 F350.23.0026V01 kits are required for a 3 stops' lift, the brackets being positioned as per the sample drawing.

The following procedure explains the correct use of chemical bolts in case of solid bricks:

Bolt features			
Bar threading	Ø b	mm	M10
Total bar length	L	mm	110
Space to be closed	S	mm	max 15
Hole preparation			
Nominal bit diameter	Ø f	mm	10
Drilling depth	P	mm	≥ 140
Bar insertion depth	h _v	mm	≈ 75
Resin filling volume		≈ 3/4 hole (≈ 18÷28 ml)	



HOLLOW BRICKS

The special kit F350.23.0025V01 for chemical bolts application is composed of:

- n° 16 zinc coated **THREADED BARS** M10x110, 45° cut (anti rotation);
- n° 2 300 ml vinyl ester **CARTRIDGES** (styrene free), suitable for elevated loads and application in humid holes, to be used with standard caulking guns;
- n° 2 multipurpose **MIXERS** $\varnothing 9$ mm, additionally to the 4 mixers foreseen for the cartridges;
- n° 2 **NET COVERED** bolts $\varnothing 16$ mm, length 1 mt each.

Each kit is sufficient for 8 brackets, required for approx. 1 stop.

For instance, 3 F350.23.0025V01 kits are required for a 3 stops' lift, the brackets being positioned as per the sample drawing.

The following procedure explains the correct use of chemical bolts in case of hollow bricks:

Bolt features			
Net bolt	$\varnothing \times L$	mm	16 x 100
Bar threading	$\varnothing b$	mm	M10
Total bar length	L	mm	110
Space to be closed	S	mm	max 15
Hole preparation			
Nominal bit diameter	$\varnothing f$	mm	16
Drilling depth	P	mm	≥ 140
Bar insertion depth	hv	mm	≈ 75
Resin filling volume		$\approx 3/4$ del foro ($\approx 18 \div 28$ ml)	

