


SimpLift®

in Cross 50.2 structure and masonry shaft

*Electric screw driven Homelift
with car*

INSTALLATION AND COMMISSIONING INSTRUCTIONS

(Rev.0)



sample image

0	First edition	09.11.2022
Rev.	Description	Date

TABLE OF CONTENTS

1. Manual reading guide	8
1.01. Preliminary information	8
1.02. Personal security and risk recognition	9
3. Safety and information Signs	10
3.01. DANGER Signs	10
3.02. PROHIBITION Signs	10
3.03. MANDATORY Signs	10
3.04. Information symbols and infographics	10
4. Manual reading guide	11
4.01. Preliminary information	11
5. Manual reading guide	12
5.01. Preliminary information	12
6. Tools required for installation	13
7. Preliminary checks and shaft preparation	15
8. Installing the scaffold	16
9. Load lifting devices	17
10. Box content - screws kit	18
11. Steel structure	22
11.01. Upright recognition and positioning	22
11.02. Transom - recognition and positioning	24
11.03. Shell - installation	25
11.03.01 SHELL - ELEMENT IDENTIFICATION	25
11.03.02 SHELL - FASTENER IDENTIFICATION	25
11.03.03 BASEMENT PERIMETER ASSEMBLY - INSTALLATION AND ANCHORING	26
11.03.04 REINFORCEMENT PLATES - INSTALLATION	29
11.03.05 SHELL - INSTALLATION (GUIDE RAIL SIDE)	30
11.03.06 SHELL - IDENTIFICATION OF THE GUIDE RAIL SIDE TRANSOMS	31
11.03.07 SHELL - INSTALLATION (SIDE OPPOSITE TO THE GUIDE RAILS)	33
11.03.08 DOOR TRANSOM INSTALLATION	35
11.03.09 DOOR TRANSOM ON TOP OF JAMB JOINT - INSTALLATION	36
11.04. Mechanics infill rear panels - installation	37
11.05. Shell roof - installation (flat / sloping roof)	38
11.05.01 SHELL ROOF - PRE-INSTALLATION OF CORNER PLATES	38
11.05.02 OUTDOOR ROOF - SIDE-MEMBER INSTALLATION	38
11.05.03 INDOOR ROOF - SIDE-MEMBER INSTALLATION	39
11.05.04 BRACKETS FOR SHELL TIE-RODS (SPIDERS) - INSTALLATION	39
11.05.05 SHELL TIE-RODS (SPIDERS) - INSTALLATION	40
11.06. Shell - anchoring	43

11.06.01	WALL anchoring	43
11.06.02	PIT anchoring	43
12.	Mechanics - installation	44
12.01.	Guide rail supports - installation	44
12.02.	Pit bottom template - installation	46
12.03.	Guide rails	48
12.03.01	GUIDE RAILS - PRELIMINARY OPERATIONS	48
12.03.02	GUIDE RAILS - PUTTING INTO PLACE AND FASTENING	50
12.03.03	GUIDE RAILS - JOINT	53
12.04.	Sensor and flat cable support bars - installation	54
12.05.	Headroom beam and transoms - installation	55
12.06.	System installation in masonry shaft	56
12.06.01	PIT BOTTOM TEMPLATE - GROUND ANCHORING	56
12.06.02	Guide rails - wall anchoring	56
12.06.03	HEADROOM BEAM - WALL FASTENING (MASONRY SHAFT ONLY)	57
12.07.	Shell - plumb / wall anchoring	58
13.	Electrical system - preliminary checks	59
13.01.	Electrical system upstream of the platform - preliminary arrangements	59
14.	Mechanics - installation	60
14.01.	Geared motor - installation	60
14.02.	Pit stop - installation	60
14.03.	Safe Pit - installation	61
14.04.	Flat cables - installation and connection	62
14.05.	Magnet support brackets - contacts - ramps	63
14.06.	Manoeuvring screw - checks and precautions	65
14.07.	Manoeuvring screw - preliminary operations	66
14.07.01	SCREW SLEEVE (IN PIT)	66
14.07.02	MANOEUVRING SCREW PRE-ASSEMBLY	66
14.08.	Safety contact in the headroom	67
14.09.	Nut screw - check for wear and tear	68
14.10.	Sling (with mechanics) - preliminary operations	70
14.11.	Sling (with mechanics) - handling	71
14.12.	Sling (with mechanics) - installation	72
14.12.01	SHOES - PROPER POSITIONING	75
14.13.	Manoeuvring screw - installation	76
14.13.01	STANDARD installation	76
14.13.02	installation in case of pre-assembled screw (§ 13.07.02)	77
14.14.	Car floor - handling/putting into place	79
14.15.	Car floor - fastening and adjustment	80
14.16.	Car operation panel (COP) - temporary installation	81

14.17. Shell infills - installation	82
14.18. Automatic sliding doors - installation	83
14.18.01 DOOR FASTENING BRACKETS - IDENTIFICATION	83
14.18.02 DOOR FASTENING BRACKETS - installation	84
14.19. Swing doors - installation	85
14.19.01 shell - preliminary operations	85
14.19.02 shell - preliminary operations	86
14.20. Shaft electrical system - installation	87
14.20.01 WIRING - INSTALLATION	87
14.20.02 MAGNETS FOR SENSORS - INSTALLATION	87
14.21. Car - installation	88
14.21.01 SUPPORT BRACKET - INSTALLATION	88
14.21.02 CAR ROOF - FRAME - INSTALLATION	89
14.21.03 Car jambs and electronic barrier - Installation	90
14.21.04 FRONT TIE-RODS AND ROOF TIE-RODS - Installation AND CAR PLUMBING	91
14.21.05 Wall opposite to the mechanics - installation	92
14.22. Automatic sliding doors - installation	93
14.22.01 DOOR OPERATORS - installation	93
14.23. Automatic sliding doors - installation	95
14.23.01 THRESHOLD SUPPORT - installation	95
14.24. Swing doors - installation	96
14.24.01 THRESHOLD SUPPORT - installation	96
14.25. Car electrical connections	97
14.25.01 CAR CONTROL BOARD (UCEC.C) - CONNECTION	97
14.26. Mechanics side wall and car operation panel - Installation	98
14.26.01 MECHANICS SIDE WALL - INSTALLATION	98
14.26.02 CAR OPERATION PANEL (COP) WITH SAFETY CONTACT - INSTALLATION	98
14.27. Wall with mirror and handrail - Installation	99
14.27.01 WALL - INSTALLATION	99
14.27.02 MIRROR - INSTALLATION	99
14.28. Car counter-ceiling - Installation	101
14.28.01 CAR COUNTER-CEILING (WITH SAFETY CONTACT) - INSTALLATION	101
14.29. Car doors - Panels - Installation	102
14.29.01 SLIDING PANELS - INSTALLATION	102
14.30. Electric connections for first start-up	103
14.30.01 COLLEGAMENTI ELETTRICI DI VANO	104
14.30.02 COLLEGAMENTI ELETTRICI DELLE PORTE	105
14.31. Operations to be performed before operating the platform	106
14.32. Landing door - adjustments	107

14.32.01	LANDING DOOR - STOP ADJUSTMENT.....	107
14.33.	Shaft in structure - assembly	108
14.33.01	IN STRUCTURE SHAFT (WITH SIDE INFILL) - ASSEMBLY.....	108
14.34.	Control cabinet	110
14.34.01	CONTROL CABINET - ASSEMBLY	110
14.34.02	CONTROL CABINET - CABLE ROUTING.....	111
14.34.03	ARMADIO QUADRO ELETTRICO - CHIUSURA FORO MONTANTE	113
14.34.04	SAFE-PIT - EXTERNAL CONTROL LEVER CONNECTION	114
15.	Infills	115
15.01.	Infills - preliminary operations	115
15.02.	Infill - silicone application for outdoor use	116
15.03.	Structure infills - correct positioning	117
15.04.	Infill under the floor door (different from ground floor)	118
15.05.	Structure and mechanics infills - assembling.	119
1.1.01	Structure infills - PREPARATION AND ASSEMBLY	119
1.	Additional installations	120
1.01.	Protective canopy (if supplied).....	120
1.02.	Structure - anchoring by ties (optional).....	121
1.02.01	ANCHORING TIES - PREPARATION	121
1.02.02	ANCHORING TIES - WALL ANCHORING	122
17.	First test travel	123
18.	Assembly and completion adjustments of the platform	124
18.01.	Overload - adjustment.....	124
19.	Manual reading guide	125
20.	Final checks and adjustments	128
21.	Platform noise.....	128

IMPORTANT INFORMATION

1. Manual reading guide

IMPORTANT!

**EN: Translation of the original instructions**

This product may only be commissioned if these instructions are available to you in an official EU language that you understand and you have understood the contents.
If this is not the case, please contact your Lifting Italia S.r.l. contact partner.

READ THIS MANUAL CAREFULLY

BEFORE INSTALLING AND USING THE PRODUCT

Retain the technical documentation near the lifting platform for the entire lifecycle of the product. In case of change of ownership, the technical documentation must be provided to the new user as an integral part of the product.

1.01. Preliminary information

NOTICE



This product must be installed and put into operation according to the provisions and regulations in force. Improper installation or improper use of the product can cause damage to people and property, as well as cause the warranty to lapse.

FOLLOW THE SUGGESTIONS AND RECOMMENDATIONS TO OPERATE IN SAFETY.

Any unauthorized modification can compromise the safety of the system, as well as the correct operation and the life of the machine. If you have any doubts regarding the correct understanding of the information and contents contained in this manual, contact LIFTING ITALIA S.r.l. immediately.

QUALIFIED PERSONNEL.

The product covered by this documentation can only be installed by qualified personnel, in compliance with the attached technical documentation, above all in compliance with the safety warnings and the precautions contained therein.



Technical specifications may be subject to change without notice due to product improvement development.

The drawings included in this manual are to be considered as indicative and are NOT an exact reference to the product concerned.

1.02. Personal security and risk recognition

This manual contains safety rules that must be observed to safeguard personal safety and to prevent damage to the property.

The indications to be followed to guarantee personal safety are highlighted by a triangle symbol while those to avoid material damage are not preceded by the triangle. The hazard warnings are shown as follows and indicate the different levels of risk in descending order.

RISK CLASSIFICATION AND RELATIVE GRAVITY OF DAMAGE		
DANGER!	The symbol indicates that the failure to comply with appropriate safety measures causes death or serious physical injury.	RISK LEVEL
WARNING	The symbol indicates that the failure to observe the corresponding safety measures can cause death or serious personal injury.	
CAUTION	The symbol indicates that failure to observe the relevant safety measures can cause minor or moderate personal injury or damage to the device.	
NOTICE	It is not a symbol of security. It indicates that the failure to comply with relevant safety measures can result in property damage.	
INFORMATION	It is not a symbol of security. It indicates important information.	







If there are multiple levels of risk, the danger warning always indicates the highest one. If a warning is drawn with a triangle to warn to the risk of injury to persons, the risk of possible property damage may also be caused at the same time.

WARNING	
	During installation / maintenance of the platform, the safety functions are temporarily suspended. Therefore all necessary precautions must be taken to avoid personal injury and / or damage to the product.

IMPORTANT INFORMATION

3. Safety and information Signs






3.01. DANGER Signs

	GENERAL DANGER		ELECTRICITY DANGER		DANGER FLAMMABLE MATERIAL
	DANGER OF FALL BY A LEVEL		DANGER SUSPENDED LOADS		DANGER OF CRUSHING










3.02. PROHIBITION Signs

	GENERIC PROHIBITION		FORBIDDEN TO STEP ON		PROHIBITED TO WALK ON OR STOP IN THIS AREA
---	---------------------	---	----------------------	---	--

3.03. MANDATORY Signs

	OBLIGATORY TO WEAR THE PROTECTION HELMET		OBLIGATORY TO WEAR SAFETY SHOES		OBLIGATORY WEAR THE PROTECTIVE GLOVES
	OBLIGATORY TO WEAR EYE PROTECTION		OBLIGATION TO WEAR THE AUDIO PROTECTION		

3.04. Information symbols and infographics

	MARK		DRILL AND/OR SCREW		CUTTING AND/OR GRINDING
	MEASURE		APPLY RIVETS		USE SUCTION CUPS
	USE THE HAMMER		LEVELING		USE HOIST



INFORMATION

Symbol that identifies information that is useful to the installer but is not mandatory for the installation, nor does it pose a risk to the user.



IMPORTANT!

Symbol that identifies important information to be scrupulously observed.



ELECTRICAL CONNECTIONS

Symbol that identifies the connection of an electrical component.

4. Manual reading guide

IMPORTANT!



EN: Translation of the original instructions

This product may only be commissioned if these instructions are available to you in an official EU language that you understand and you have understood the contents.
If this is not the case, please contact your Lifting Italia S.r.l. contact partner.

READ THIS MANUAL CAREFULLY

BEFORE INSTALLING AND USING THE PRODUCT

Retain the technical documentation near the lifting platform for the entire lifecycle of the product. In case of change of ownership, the technical documentation must be provided to the new user as an integral part of the product.

4.01. Preliminary information

NOTICE



This product must be installed and put into operation according to the provisions and regulations in force. Improper installation or improper use of the product can cause damage to people and property, as well as cause the warranty to lapse.

FOLLOW THE SUGGESTIONS AND RECOMMENDATIONS TO OPERATE IN SAFETY.

Any unauthorized modification can compromise the safety of the system, as well as the correct operation and the life of the machine. If you have any doubts regarding the correct understanding of the information and contents contained in this manual, contact LIFTING ITALIA S.r.l. immediately.

QUALIFIED PERSONNEL.

The product covered by this documentation can only be installed by qualified personnel, in compliance with the attached technical documentation, above all in compliance with the safety warnings and the precautions contained therein.



Technical specifications may be subject to change without notice due to product improvement development.

The drawings included in this manual are to be considered as indicative and are NOT an exact reference to the product concerned.

IMPORTANT INFORMATION

5. Manual reading guide

IMPORTANT!

**EN: Translation of the original instructions**

This product may only be commissioned if these instructions are available to you in an official EU language that you understand and you have understood the contents.
If this is not the case, please contact your Lifting Italia S.r.l. contact partner.

READ THIS MANUAL CAREFULLY

BEFORE INSTALLING AND USING THE PRODUCT

Retain the technical documentation near the lifting platform for the entire lifecycle of the product. In case of change of ownership, the technical documentation must be provided to the new user as an integral part of the product.

5.01. Preliminary information

NOTICE



This product must be installed and put into operation according to the provisions and regulations in force. Improper installation or improper use of the product can cause damage to people and property, as well as cause the warranty to lapse.

FOLLOW THE SUGGESTIONS AND RECOMMENDATIONS TO OPERATE IN SAFETY.

Any unauthorized modification can compromise the safety of the system, as well as the correct operation and the life of the machine. If you have any doubts regarding the correct understanding of the information and contents contained in this manual, contact LIFTING ITALIA S.r.l. immediately.

QUALIFIED PERSONNEL.

The product covered by this documentation can only be installed by qualified personnel, in compliance with the attached technical documentation, above all in compliance with the safety warnings and the precautions contained therein.











Technical specifications may be subject to change without notice due to product improvement development.

The drawings included in this manual are to be considered as indicative and are NOT an exact reference to the product concerned.

6. Tools required for installation

BALL POINT LONG HEX KEY WRENCH 	ELECTRICIAN SCREWDRIVER SET 	HAMMER + RUBBER HAMMER 	TAPE MEASURE 
SPIRIT LEVEL 	SCISSORS FOR ELETTRICIANS 	SPANNER + SOCKET WRENCH 	RACKETING RING SPANNER SET 
PLIERS WRENCH 	PORTABLE LAMP 	SAFETY LADDER 5 STEPS 	LIFTING BELTS 
DRILL + ELECTRIC SCREWDRIVER 	DRILL BITS 	CORNER GRINDER 	CUT-OFF AND GRINDING WHEELS 



7. Preliminary checks and shaft preparation

IMPORTANT!



The checks can only be carried out by direct confirmation with the final GAD in its latest approved revision.


- Check the vertical free dimensions along the entire shaft, in vertical projection of the pit, as indicated on the GAD.
- Check that the dimensions of the pit, storey heights and headroom are the same as those specified in the GAD.

IMPORTANT!



The GAD indicates the permissible deviation tolerances from the nominal dimensions.

A = PIT
B = LANDING STOP
C = HEADROOM




- Check that the fixings of the structure / guide rails can be realized at the points specified in the GAD, by direct fixing to a load-bearing wall or tie.

WARNING



FAILURE TO OBSERVE THE DISTANCE BETWEEN ANCHOR POINTS COULD COMPROMISE THE STABILITY OF THE PLATFORM!

The distance between the fixing points cannot for any reason exceed the dimensions indicated in the project.



9. Load lifting devices

WARNING





DANGER SUSPENDED LOAD:

The use of load lifting devices involves risks, therefore the safety instructions provided by the lifting device manufacturer must be followed.

The masonry work to prepare the slab for installing the hook must be carried out in accordance with the regulations in force.

For the handling of loads inside the shaft, we recommend:

- ① The use of a jib winch/jib hoist to be anchored to the scaffold (recommended for shafts with an open header in structure or masonry).
- ② The use of a winch/hoist to be hung from an approved hook provided in the ceiling of the header (recommended solution for masonry shafts with closed header)..



TIPS FOR LIFTING LOADS INSIDE THE SHAFT:

WINCH AT HEIGHT

- Check the compatibility of the forces applied with the requirements of the scaffold tower manufacturer and/or the manufacturer of the jib used..
- Install the jib (crane) ① at the highest point of the scaffold.

IMPORTANT!



The images and information provided here are purely indicative and are intended to assist the installer in his work. Always refer to the appropriate technical documentation.

10. Box content - screws kit




Each box with its identification code represents how many pieces per item are contained in each package (KIT).


F353.23.0006




F353.23.0004




F353.23.0002




F353.23.0007




F353.23.0010




D003.23.0001




F353.23.0017




F353.23.0008




F353.23.0009




S001.23.0002



S001.23.0001




F353.23.0011




S001.23.0004




S001.23.0010




F353.23.0012




S000.23.0012




S000.05.5006




F355.23.0001




F355.23.0002




F355.23.0003




F355.23.0004




F355.23.0005



F355.23.0006



F355.23.0007



NOTICE



FOLLOW THE TIGHTENING TORQUES INDICATED FOR THREADED COUPLINGS.

In order to avoid the risk of bolt or component loosening or stress, with a deformation and breakage risk, please follow the screw tightening torques indicated in the table.

TIGHTENING TORQUE GUIDE		
SCREW	COUPLE MAX (Nm)	COUPLE MIN (Nm)
M3	1.2	1.0
M4	2.6	2.1
M5	5.1	4.1
M6	9.0	7.0
M8	21.0	17.0
M10	42.0	34.0
M12	71.0	57.0
M16	175.0	145.0


11. Steel structure

11.01. Upright recognition and positioning

IMPORTANT!



PIT UPRIGHTS BEAR THE LETTER "P" ENGRAVED ON THE INNER SIDE.
HEADER UPRIGHTS BEAR THE LETTER "T" ENGRAVED ON THE INNER SIDE.
INTERMEDIATE UPRIGHTS ARE NEUTRAL AND INTERCHANGEABLE.
The arrangement of letters for the correct layout is indicated on the design drawing.



NOTICE





ALWAYS ADHERE TO THE INSTALLATION DIAGRAM AS SHOWN ON PROJECT DRAWING.
 NOTE: Pit and header uprights have a fixed position, while intermediates are symmetrical.



MACHINE SIDE

OPPOSITE SIDE OF THE MACHINE




HEADROOM JAMBS




INTERMEDIATE JAMBS




PIT JAMBS




HEADROOM JAMBS



INTERMEDIATE JAMBS



PIT JAMBS




11.02. Transom - recognition and positioning

IMPORTANT!



THE TRANSOMS are marked in the attachment side by 1 (•), 2 (••) or 3 (•••) perforations indicating the position of the transom (mechanical side, side, opposite). Follow the indications on the design drawing for proper positioning.



11.03. Shell - installation

11.03.01 SHELL - ELEMENT IDENTIFICATION

EXAMPLE CONFIGURATION:


- (A) FLOOR 0 ACCESS SIDE
- (B) SIDE OPPOSITE TO THE MECHANICS
- (C) SIDE ADJACENT TO THE MECHANICS
- (D) MECHANICS SIDE







NOTE: The mechanics can be installed in the (B), (C) and (D) sides.


(M) JAMBS - MECHANICS SIDE

(N) JAMBS - SIDE OPPOSITE TO THE MECHANICS



11.03.02 SHELL - FASTENER IDENTIFICATION

	GUIDE RAIL TRANSOM PLATE
	SIDE TRANSOM PLATE
	TRANSOM PLATE
	DOOR PLATE (not shown in the diagram to the side, see § 10.03.07)



11.03.03 BASEMENT PERIMETER ASSEMBLY - INSTALLATION AND ANCHORING

NOTICE






ALWAYS OBSERVE THE INSTALLATION DIAGRAM, AS SHOWN IN THE DESIGN DRAWING.

NOTE: The pit and headroom jams have a fixed position, while the intermediate ones are symmetrical.

- ❶ Lay the first basement perimeter assembly as shown in the design drawing.
- ❷ We recommend that you start by laying the first pit jamb on the guide rail side **A** and the two adjacent jams **B**.
- ❸ Fasten the transoms to the jams using the relevant KITS.

FLOOR 0 THRESHOLD TRANSOM




M12x30




S001.23.0001




- 5 Install the jamb opposite to the guide rail side **C** and the subsequent transom **D**.
- 6 As mentioned above, fasten the transoms and jambs using the relevant KITS.



- 7 Install the subsequent jambs and transoms **E F G**.
- 8 Level the assembly using the supplied spacers, if necessary.
- 9 Anchor the jambs to the wall.











- 10 Accurately measure the diagonals to verify that the shell is level.







- 11 Fasten the L-brackets **H** to the pit jamb and transom opposite to the mechanics **I** using the supplied screws.


- 12 Anchor the assembly to the ground using the supplied plugs **J**.



11.03.04 REINFORCEMENT PLATES - INSTALLATION

Install the reinforcement plates as indicated.



	
M8x25	M6x20
	
M8	M6
S001.23.0001	



11.03.05 SHELL - INSTALLATION (GUIDE RAIL SIDE)

- 1 Insert the jamb joint plate into the jamb **(A)**, temporarily fasten it with a kit screw **(B)**, then insert the next jamb segment **(C)**.
- 2 Fasten the transoms to the jambs using the supplied screws, inserting them into the rivet nuts that are present in the jamb **(E)** joint plate.
- 3 Check that the distance between the transoms is **965 mm**
- 4 If the jamb joint does not correspond to the presence of transoms (presence of a floor door), fasten the jamb joint plate using the flanged 8x25 hex socket screws included in the KIT **(F)**.

For the installation of the door transoms, refer to § 10.03.09.




11.03.06 SHELL - IDENTIFICATION OF THE GUIDE RAIL SIDE TRANSOMS



IMPORTANT!



CHECK THAT THE TRANSOM INSTALLATION DIRECTION IS CORRECT





In a single access system with automatic doors, the guide rails are offset, and the relevant fasteners on the **mechanics side transoms** are correspondingly offset. For this reason, they must be installed in the right direction, which is indicated by the arrows as shown below (REFER TO THE GAD).

- ① In the above-mentioned case, the mechanics side jambs have arrows etched on them , that indicate the offset direction (to be verified on the GAD).




To join jambs and transoms, use the supplied joint brackets, following the instructions provided below.




SIDE ADJACENT TO THE MECHANICS



MECHANICS SIDE - STANDARD JAMBS




MECHANICS SIDE - JAMB JOINT



11.03.07 SHELL - INSTALLATION (SIDE OPPOSITE TO THE GUIDE RAILS)

- ① Insert the jamb joint plate into the jamb **A**, temporarily fasten it with a kit screw **B**, then insert the next jamb segment **C**.
- ② Fasten the transoms to the jambs using the supplied screws, inserting them into the rivet nuts that are present in the jamb joint plate **E**.
- ③ If the jamb joint does not correspond to the presence of transoms (presence of a floor door), fasten the jamb joint plate using the flanged 8x25 hex socket screws included in the KIT **F**.


For the installation of the door transoms, refer to § 10.03.09.






To join jambs and transoms, use the supplied joint brackets, following the instructions provided below.

INSERTI FILETTATI AD ESPANSIONE - DETTAGLIO




JOINT PLATE FASTENING - DETAIL






JAMB JOINT

JOINT PLATE FASTENING - DETAIL




STANDARD JAMBS

JOINT PLATE FASTENING - DETAIL





11.03.08 DOOR TRANSOM INSTALLATION

- In the top transom the slots must be oriented downwards **1**
- In the bottom transom the slots must be oriented upwards **2**






11.03.09 DOOR TRANSOM ON TOP OF JAMB JOINT - INSTALLATION

- In the top transom the slots must be oriented downwards
- In the bottom transom the slots must be oriented upwards




11.04. Mechanics infill rear panels - installation



- insert into the transoms the collar clips, aligning them with the relevant holes ①
- Insert the glaze supports into the collar clips ②



S001.23.0001




- Insert the rear infill panels ③
- Fasten the glazing beads using the supplied screws ④.



11.05. Shell roof - installation (flat / sloping roof)


11.05.01 SHELL ROOF - PRE-INSTALLATION OF CORNER PLATES

- ① Put into place and fasten the corner plates, **A** using the supplied screws.




11.05.02 OUTDOOR ROOF - SIDE-MEMBER INSTALLATION

- ② Put into place and fasten the support side-members for outdoor roof **B** + **C**, using the supplied screws.




11.05.03 INDOOR ROOF - SIDE-MEMBER INSTALLATION

- ② Put into place and fasten the support side-members for outdoor roof ②, using the supplied screws.







11.05.04 BRACKETS FOR SHELL TIE-RODS (SPIDERS) - INSTALLATION

- ③ Put into place and fasten the L-brackets supporting the headroom tie-rods ③, using the supplied screws, as shown.




11.05.05 SHELL TIE-RODS (SPIDERS) - INSTALLATION


- ④ Insert the tie-rod (threaded bar) **E** and fasten it with the nuts, ensuring that it remains tensioned.
- ⑤ Should the bar **E** protrude from the bracket, cut off the excess segment.






- ⑥ Insert into the side members (B + B or B + C according to the roof type) the reinforcement bars F.
- ⑦ Drill the bar using the side holes of the side-members as a template G.



- ⑧ Rivet all the reinforcement bars to the side-members.




- 9 Put into place the outer covers **H** and rivet them to the reinforcement bars and to the side-members.



- 10 Carefully seal the joints with silicone, to prevent any leaks.


- 11 Put into place and rivet the cover joint profile **I**.




11.06. Shell - anchoring

11.06.01 WALL ANCHORING

- Carry out the anchoring operations in the transom **1** or in the jamb **2** as indicated in the design drawing
- If the wall is not perfectly straight, use spacers **3**.




11.06.02 PIT ANCHORING





12. Mechanics - installation

12.01. Guide rail supports - installation


- ① Insert the guide rail transom fastening brackets **A** into the rear mechanics transoms.
- ② Secure the brackets **A** with the screws provided.



- ③ Put into place and fasten the guide rail support transom **B**, aligning it with the fastening threaded inserts, using the relevant brackets **C**.



- ④ Insert the i cage nuts into the relevant holes on the anchoring brackets.




12.02. Pit bottom template - installation

IMPORTANT!



Refer to the GAD and to § 10.03.06 - SHELL - IDENTIFICATION OF THE GUIDE RAIL SIDE TRANSOMS, and check the proper installation direction of the transoms and of the pit bottom TEMPLATE.

- 1 Put the pit bottom template into place, **A** checking that its dimensions match those indicated on the design drawing (GAD).
- 2 Make sure that THE TEMPLATE is perfectly level **A**, using the supplied spacers (+/- 2 mm) **B**.





We recommend using the laser level to help you level the template correctly.

- 3 Anchor the TEMPLATE (A) through the existing holes, using the supplied expansion plugs (C).
- 4 Anchor the guide rail support brackets (D) through the existing holes, using the supplied expansion plugs (C).



M12x125

F353.23.0001




3



M6x16

F355.23.0006


4





12.03. Guide rails

12.03.01 GUIDE RAILS - PRELIMINARY OPERATIONS


- ① Insert the guide rail joining elements **A** into the jamb housings



- ② Secure with the spring pins and screws provided



- ③ Insert the cage nuts into the relevant holes, already drilled in all the guide rail segments **B**.



12.03.02 GUIDE RAILS - PUTTING INTO PLACE AND FASTENING


IMPORTANT!





FOR PROPER INSTALLATION:

- **CHECK** that the dimensions and the location match those indicated on the design drawing (GAD).
- Install the guide rails, the screw and the platform with utmost precision, to prevent future malfunctions.
- Carry out the adjustments and alignments during the installation stage (they can only be performed on the machine at the installation site). *The accuracy of these adjustments ensures a smooth, quiet, vibration-free stroke.*
- The longer the travel, the more care must be taken when adjusting.
- For optimal results, follow all the instructions included in this manual.
- **CAREFULLY CHECK** the alignment of guide rails, screws, pins, and platform shoes, as well as the lubrication of the screw and of the guide rails. These checks are particularly important to ensure that the platform will operate properly.




- ① Put the pit bottom template into place, **A** checking that its dimensions match those indicated on the design drawing (GAD).







- ② Put the guide rails into place in the template housing **B**, so that the holes are aligned with those on the template.



- ③ Fasten the guide rails to the template, using the supplied self-threading screws **C**.




- 4 Fasten all the guide rail segments **D** using the supplied screws, checking that they are properly aligned.






12.03.03 GUIDE RAILS - JOINT

- 1 Insert the pre-assembled segments **A** (§ 11.03.01 GUIDE RAILS - PRELIMINARY OPERATIONS) as shown and fasten them using the supplied screws and spring pins **B**.





12.04. Sensor and flat cable support bars - installation

- Put the bars into place and fasten them using the relevant steel rivets.









The sensor and flat cable support bars must be installed **840 mm** above the floor thresholds.

12.05. Headroom beam and transoms - installation

CAUTION			WEAR APPROPRIATE PPE		
	CRUSHING HAZARD Handle the components using a suitable lifting equipment (see Chap. 9).				




- Put into place the headroom beam in the position indicated by the holes, using a hoist, and secure it to the guide rails using the screws supplied in the KIT ①.



12.06. System installation in masonry shaft




12.06.01 PIT BOTTOM TEMPLATE - GROUND ANCHORING

- Anchor the template to the floor, through the existing holes, using the supplied plugs **1**.




12.06.02 GUIDE RAILS - WALL ANCHORING

- Put the brackets into place and anchor them to the wall through the pre-drilled holes, using the supplied plugs **2** + **3** (optional).
If necessary, use the supplied spacers to level them before anchoring them.





12.06.03 HEADROOM BEAM - WALL FASTENING (MASONRY SHAFT ONLY).





- Position the wall anchor brackets above the headroom beam.




- Drill the wall at a position corresponding to the holes in the brackets.
- Anchor the brackets with the plugs provided.



- Drill the headroom beam at a position corresponding to the holes in the brackets.
- Secure the brackets to the beam with the rivets provided.





- Proceed with the installation of the last transom in the headroom as previously seen.



12.07. Shell - plumb / wall anchoring

- Check the horizontal and vertical position of the installed guide rails so that they are plumb (in both directions), with a maximum deviation of $\pm 2\text{mm}$ at each point.




13. Electrical system - preliminary checks

13.01. Electrical system upstream of the platform - preliminary arrangements

- The client will have to provide, for the Power Supply Panel, protection devices that are suitable for the electrical power distribution system and for the relevant short-circuit current, in accordance with the standard CEI 64-8 and following (adequately sized thermal magnetic switch and 30mA residual current protection).
- The main switch cutting off the motive power, also supplied by LiftingItalia, is installed inside the control panel of the platform.
-

After installing the power supply panel, record the check completion as indicated at point 4.01.01 of the manual "IM.TEC.127 - DOMOFLEX-2 - Final Checks".



WARNING



ELECTROCUTION RISK:

The lighting and power supply systems must meet the requirements of the system and of the regulations in force. Check that they are properly grounded. Should they fail to meet the requirements, stop the installation until the Client has ensured that they comply with the regulations.

14. Mechanics - installation



14.01. Geared motor - installation





FOR OPTIMAL CENTRING AND TO AVOID VIBRATIONS:

Before fully tightening the screws, complete the platform installations. Then, with the platform at the lowest floor, fully tighten the screws to the prescribed tightening torques (page 15).

- Position and secure the geared motor with its support on the template with the screws provided.




- Position the geared motor protection plate and secure it to the template, using the screws provided.



14.02. Pit stop - installation

- Position the pit stop and secure it to the template with the screws pre-mounted on the component.



14.03. Safe Pit - installation

CAUTION




BEFORE ACCESSING THE PIT

Install the Safe Pit safety device to ensure safe operation in the pit.





- Place the Safe Pit on the template at the bottom of the pit: the strut must rest on the template and fit into the prearranged pin.
- Secure the Safe Pit using the rivets provided.



M4.8x11

F353.23.0005



WARNING




CRUSHING HAZARD




The strut must be opened/closed manually until the door, containing the control lever, is installed.

PERICOLO



CLOSED (OFF) SAFE PIT

IN SICUREZZA



OPEN (ON) SAFE PIT

14.04. Flat cables - installation and connection





The flat cable is pre-assembled on the platform wall.

The exact height of the bracket is specified in the supplied installation diagram.

- Position the flat cable support bracket **A** on the transom positioned at a height equal to

$$H > \frac{\text{travel}}{2}$$

with respect to the lowest access.



- Unwind the flat cable from the platform wall and secure it to the flat cable support bracket **A** on the transom.
- Route the flat cable toward the pit template and secure it by positioning the brackets provided.
- Fasten the flat cable to the transoms approximately every 2 m with cable clips, as indicated in **B**

IMPORTANT!




Route the flat cable so that the folds are soft and do not damage the cable.




F353.23.0007

CAVO PIATTO - FISSAGGIO A TRAVERSO - DETTAGLIO



CAVO PIATTO - FISSAGGIO A DIMA - DETTAGLIO



14.05. Magnet support brackets - contacts - ramps




Pay attention to the positioning of the magnet support brackets:


IN THE HEADROOM, the bracket with the overtravel contact must be positioned facing down (bottom overtravel).

ALONG THE SHAFT, the brackets (if any) should be placed WITHOUT the pre-assembled contact.

IN THE PIT, the bracket with the overtravel contact must be positioned facing up (top overtravel).



- Position the magnet support brackets so that the centre of the bracket (identified by the reference notch) is at a distance of 840 mm from the floor level.
- Adjust the position of the magnets (IS, ID and IR) as shown in the figure: the magnet support plate is provided with holes to ease magnet alignment.




The IR magnet is located on the lowest access only.

- Repeat the procedure for each access.



The control lever for Safe Pit remote activation/deactivation is pre-mounted in the cabinet of the electrical panel located in the door jamb.

To connect it to the device, see Paragraph:
11.13.04 SAFE PIT - CONNECTION OF THE EXTERNAL CONTROL LEVEL.



14.06. Manoeuvring screw - checks and precautions


NOTICE




ALWAYS CHECK THE INTEGRITY OF THE MANOEUVRING SCREW.

Before and after assembling the manoeuvring screw segments, make sure that there are no damages, metal burrs or protruding parts.


VITE DI MANOVRA - DETTAGLIO SBAVATURA



VITE DI MANOVRA - DETTAGLIO SBAVATURA





VITE DI MANOVRA - RIMOZIONE SBAVATURE



14.07. Manoeuvring screw - preliminary operations

14.07.01 SCREW SLEEVE (IN PIT)

- ① Insert the tab **A** into the sleeve housing **B**.
- ② Insert the sleeve **B** into the geared motor hub **C**.



14.07.02 MANOEUVRING SCREW PRE-ASSEMBLY



- ③ When possible (if there is enough space in the headroom), we recommend that you pre-assemble the screw segments **D**, to optimise the accuracy of the assembly.



CHECK the design drawing for the length of the individual segments and the correct installation sequence.

The installation of the manoeuvring screws must be performed from the bottom upwards: **V1 > V2 > V3**.

NOTE: The **V2** segment is not always present.






WARNING

ANY PROTRUDING PINS MAY PREJUDICE THE MACHINE SAFETY.




Make sure that the **fastening pins DO NOT protrude** from their seat on both sides.



14.08. Safety contact in the headroom

- Place the headroom safety contact on the headroom beam.



14.09. Nut screw - check for wear and tear


CAUTION



IMPORTANT SAFETY ADJUSTMENTS



The provisions contained in this paragraphs are important safety adjustments, and must be strictly observed.

- ① Access the nut screw wear contact by removing the motor casing cover **A**.



NUT SCREW WEAR CONTACT - SETTING




- ② Adjust the vertical and horizontal position of the contact **B** so that the contact head lies ~1mm from both the vertical and the sloping surface of the safety nut screw **C**.



NUT SCREW WEAR REGULATOR - SETTING

- ③ Adjust the vertical position of the safety nut screw wear regulator **B** so that its upper edge is aligned, with a tolerance of ± 0.1 mm, with the upper surface of the safety nut screw **C**.

NOTE: The vertical displacement limit, i.e., the wear limit of the drive nut screw is **MAX 2 mm** (see below)




CAUTION



NUT SCREW WEAR

- ④ If the upper edge of the wear regulator **B** moves down to the nut screw reference mark **D**, i.e., by 2 mm, replace it right away!



- ⑤ After completing the adjustments, close back the motor casing cover **A**.



If the contact cannot be adjusted to a proper position, adjust the vertical position of the safety nut screw, moving it up or down by 1 or more threadings on the drive screw (the operation must be carried out after withdrawing the screw from the safety nut screw).

IMPORTANT!



THE CONTACT POSITION MUST NEVER BE CHANGED

After adjusting the contact position, never change it for any reason (except in case of contact or nut screw replacement).

If the contact and/or the nut screw are replaced, repeat the adjustment operations described above.

14.10. Sling (with mechanics) - preliminary operations



NOTICE




Position and levelling adjustment of the platform is very important: incorrect adjustment of the position and the shoes causes noises and vibrations





The car sling is supplied pre-assembled, as shown in the figure **R**.




- 1** Remove the top shoes **A** and the safety pins **B** from both sides of the pin, to ensure that it can be inserted into the guide rails.






14.11. Sling (with mechanics) - handling

CAUTION			WEAR APPROPRIATE PPE		
	CRUSHING HAZARD Handle the components using a suitable lifting equipment (see Chap. 9).				

- ① To handle/lift the platform components, we recommend that you use a winch/hoist anchored to the headroom (see Chap. 8), a lifting beam **A** and a set of lifting eyebolts **B**



NOTICE	
	Fasten the lifting equipment to the frame of the platform/car wall, using appropriate eyebolts or similar equipment, to avoid damaging or deforming it.
 <p>Diagram illustrating the correct attachment of the lifting equipment (red hook) to the frame of the platform/car wall using appropriate eyebolts (B).</p>	





14.12. Sling (with mechanics) - installation

IMPORTANT!





The height of the mounts on which the sling is laid must be **AT LEAST 50 mm** and **NO MORE THAN 100 mm**, in order to be able to easily insert the sling into its housing.

- 1 Put the sling into place **A** in the pit (or inside the PO shell), inserting it into the relevant discharges existing on the guide rails, holding it raised with two mounts (e.g., two wooden blocks) **B**.





M8x35

F353.23.0006




- 3** Check the sling levelling **D**. If necessary, adjust the levelling using the slots in the top shoes **E**.



TOP SHOES

- ④ Drill the shoe **E** and insert a pin into the hole already drilled on the sheet.
- ⑤ Secure the shoes by tightening the screws




WARNING





LACK OF SAFETY PINS CAN COMPROMISE THE SAFETY OF THE MACHINE.

Ensure that the safety pins are correctly installed.




- ⑥ Reinstall the safety pins **F** of the top shoes, on both sides.



14.12.01 SHOES - PROPER POSITIONING

- When placing the shoes onto the guide rails, we recommend that you interpose a 1mm spacer between them **1**, to obtain a 1mm slack that will improve the system operation.




IMPORTANT!



Make sure to remove the spacers once you have completed the platform wall installation.

Failing to remove them could damage the guide rails and the platform.



14.13. Manoeuvring screw - installation

14.13.01 STANDARD INSTALLATION



Use this installation method whenever the space in the headroom does not allow the pre-assembled screw to be lifted and inserted (§ 13.13.02).

CAUTION



CRUSHING HAZARD








Lift the screw segments using suitable lifting equipment.

WEAR APPROPRIATE PPE




- 1 Insert the screw segment **V1** into the pre-installed sleeve in the pit (§ 13.07.01) and fasten it with the supplied pins.
- 2 Insert the screw segment **V2** into the housing of the first segment and fasten it using the supplied pins.
- 3 Insert the screw segment **V3** into the headroom beam **A**.
- 4 ON THE HEADROOM BEAM **A**: position sleeve, bearing, and nut screw on the screw.
- 5 Screw in the screw segment **V3**, so that it protrudes from the headroom beam **A** by about 150 mm.

N100.40.0060




M8x30






F353.23.0008





14.13.02 INSTALLATION IN CASE OF PRE-ASSEMBLED SCREW (§ 13.07.02)

CAUTION	
	CRUSHING HAZARD Lift the screw segments using suitable lifting equipment.
WEAR APPROPRIATE PPE	
  	


- With the aid of a suitable lifting equipment (e.g., a hoist), lift the screw and insert it into the headroom beam **1**.
- ON THE HEADROOM BEAM: position sleeve, bearing, and nut screw on the screw **2**.
- Screw in the screw **3** so that it protrudes from the headroom beam by approximately 1m **4**.




- Lower the manoeuvring screw until it is inserted into the pit sleeve, passing through the motor of the mechanics assembly (platform wall) ①.
- Secure the manoeuvring screw to the headroom nut screw using the safety pin provided ②





- Secure the screw to the pit sleeve using the safety pin provided ③.





WARNING		
<p>ANY PROTRUDING PINS MAY PREJUDICE THE MACHINE SAFETY.</p>		
	<p>Make sure that the fastening pins DO NOT protrude from their seat on both sides.</p>	



14.14. Car floor - handling/putting into place

CAUTION		WEAR APPROPRIATE PPE		
	CRUSHING HAZARD Handle the components using a suitable lifting equipment (see Chap. 9).			
				

To handle/lift the platform components, we recommend that you use a winch/hoist anchored to the headroom (see Chap. 8) and a lifting beam 



14.15. Car floor - fastening and adjustment

WARNING




ANY FAILURE TO OBSERVE THE ABOVE INDICATIONS MAY PREJUDICE THE MACHINE SAFETY.

The screws must be M8x35 socket head screws **CLASS 12.9**


Observe the prescribed tightening torques. (MIN 17 Nm, MAX 21 Nm)

- ① Position the platform floor by resting it on the pit bottom
- ② Check that the platform floor is properly levelled.
- ③ Fasten the car floor **A** as shown in the figure **B**, using the supplied screws.
- ④ if necessary, adjust the floor sloping using the supplied spacers **C**.




14.16. Car operation panel (COP) - temporary installation

- ① Put into place and fasten the mechanics side **A** bottom profile.
- ② Temporarily install the car operation panel (COP) **B** to move the car during installation.



14.17. Shell infills - installation

- 1 Install all the car infills, using the car to move the material.




14.18. Automatic sliding doors - installation

14.18.01 DOOR FASTENING BRACKETS - IDENTIFICATION




Pay attention to the proper use of the fastening brackets and to their positioning.



SOPRA PORTA



STAFFA SOTTORTA - PIANI INTERMEDI









STAFFA SOTTORTA - PIANO 0



14.18.02 DOOR FASTENING BRACKETS - INSTALLATION


- ① Put the frames into place on the door transoms.
- ② Fasten the frames to the door transoms using the plates (A), (B), (C) and the supplied screws, as shown below.



14.19. Swing doors - installation

14.19.01 SHELL - PRELIMINARY OPERATIONS


- ① Insert into the door transoms the relevant fastening brackets **A**, to which the door frame will be anchored.



For the installation of the door, refer to the relevant installation manual.

14.19.02 SHELL - PRELIMINARY OPERATIONS

- 1 Put into place the infill profiles (or the individual profile) **A**, then fasten them/it using the supplied self-tapping screws.



14.20. Shaft electrical system - installation


14.20.01 WIRING - INSTALLATION



Before proceeding with the next mechanical installations, we recommend that you install all the shaft wiring, to take advantage of the absence of parts that could hinder the installation, if it was performed later.

14.20.02 MAGNETS FOR SENSORS - INSTALLATION


- ① Put into place and fasten the support transoms for the sensor magnets **T**.
- ② Carefully put into place the magnets for the sensors **M**.



14.21. Car - installation







14.21.01 SUPPORT BRACKET - INSTALLATION

- ① Install the side brackets **A** on the sling, using the supplied screws.
- ② Install the top L-brackets **B** on the sling, using the supplied screws.



14.21.02 CAR ROOF - FRAME - INSTALLATION

- 3 Put into place the roof transoms **C**, fastening them with the supplied screws **K1**.
- 4 Put into place the roof side-members **D**, fastening them with the supplied screws **K2**.
- 4 Put into place the roof front **E**, fastening it with the supplied rivets **K3**.



IMPORTANT!



CHECK THE LEVELLING

Check that the roof
frame is properly
levelled.



IMPORTANT!



CHECK THE DIAGONALS

to make sure that
the car is properly
aligned.




14.21.03 CAR JAMBS AND ELECTRONIC BARRIER - INSTALLATION

- 5 Put into place the car jambs of the mechanics side **F** and of the side opposite to the mechanics, **G** then fasten them with the supplied screws.




- 6 Pay attention to properly insert the jambs of the side opposite to the mechanics **G** into the relevant housing on the floor **H**



14.21.04 FRONT TIE-RODS AND ROOF TIE-RODS - INSTALLATION AND CAR PLUMBING

7 Insert the car tie-rods **H**, check the car plumbing and tighten the supplied nuts **I**.

8 Insert the roof tie-rods **J**, check the car plumbing and tighten the supplied nuts **K**.



IMPORTANT!



CHECK THE LEVELLING

Check that the roof
frame is properly
levelled.



IMPORTANT!







CHECK THE DIAGONALS

to make sure that
the car is properly
aligned.



14.21.05 WALL OPPOSITE TO THE MECHANICS - INSTALLATION

- 9 Put into place the car wall **L** between the opposite jambs, paying attention to properly insert it into the relevant floor housing **H**
- 10 Fasten the car wall to the car roof frame **M** using the supplied screws.




14.22. Automatic sliding doors - installation

14.22.01 DOOR OPERATORS - INSTALLATION

- ① Put into place the operator support **A** and fasten it using the supplied screws
- ② Put into place the operator brackets **B** and fasten them using the supplied screws




The screws required for the installation can be found inside the door packaging.



- 3 Put into place the operator **L** and fasten it using the supplied screws




For the door installation,
refer to the specific
manuals.



14.23. Automatic sliding doors - installation

14.23.01 THRESHOLD SUPPORT - INSTALLATION


- ① Put into place the threshold support **A** on the car basement and fasten it using the supplied screws from the rear side (under the car).




14.24. Swing doors - installation

14.24.01 THRESHOLD SUPPORT - INSTALLATION

- ① Put into place the threshold support **A** on the car basement and fasten it using the supplied screws from the front side.



- ② Put into place the sill cover **B** on the threshold support and fasten it using the supplied screws from the front side.





14.25. Car electrical connections

14.25.01 CAR CONTROL BOARD (UCEC.C) - CONNECTION

① Before fastening the car operation panel (COP), ① perform the electrical connections between the sling and the car ② (board UDEC.C).

- Plug and screw the waterproof circular connectors, making sure that they are properly tightened.
- Plug the waterproof rectangular connectors, making sure that the locking hook is properly engaged.

X	Connettore impermeabile a vite
Y	Connettore Mini Universal MATE-N-LOK





All connectors are marked with the relevant numbers/letters.

Store any excess wiring in the specific slots in the COP rear compartment.

14.26. Mechanics side wall and car operation panel - Installation



14.26.01 MECHANICS SIDE WALL - INSTALLATION

- ① Put into place the wall panels **A** and fasten them using the relevant bars **B** and the supplied screws.



14.26.02 CAR OPERATION PANEL (COP) WITH SAFETY CONTACT - INSTALLATION


- ② Put into place the car operation panel **B** and fasten it using the supplied screws



14.27. Wall with mirror and handrail - Installation



14.27.01 WALL - INSTALLATION

- ① Put into place the wall **A** and fasten it using the supplied screws




14.27.02 MIRROR - INSTALLATION



- ② Put into place the mirror supports **B** in the rectangular holes and fasten them using the supplied clips **C**.



- 3 Insert the mirror **C** into the relevant supports.





- 4 Put into place the handrail (if any) **D** and fasten it using the hardware pre-installed in the handrail itself.





14.28. Car counter-ceiling - Installation

14.28.01 CAR COUNTER-CEILING (WITH SAFETY CONTACT) - INSTALLATION

- ① Put into place the car counter-ceiling **A** and fasten it using the supplied screws




- ② Raise the counter-ceiling, **A** swivelling it on the hinges, and fasten it using the supplied screws.



14.29. Car doors - Panels - Installation

14.29.01 SLIDING PANELS - INSTALLATION

- 1 Insert the sliding panels **B** and fasten them to the operator using the screws supplied in the door kit.



14.30. Electric connections for first start-up



The electrical panel is inside the lowest access landing door jamb.
The door must be already installed (even temporarily, following safety requirements) in order to make the connections.



For electrical connections, refer to the manual IM.TEC.129 “ELECTRICAL EQUIPMENT (U.D.E.C.) INSTALLATION AND DIAGNOSTIC INSTRUCTIONS” and to the system wiring diagram.


14.30.01 COLLEGAMENTI ELETTRICI DI VANO

- Cablare i componenti elettrici mano a mano che vengono installati.
- Collegare per **ULTIMO** la dorsale di vano **A** al quadro elettrico.

AVVISO





I cavi elettrici devono passare nel vano predisposto nella guida. Una volta finito il cablaggio, è possibile installare la protezione a scatto.




AVVISO



I cavi piatti devono passare nel foro passante fra la guida e la porta contenente il quadro elettrico, in fondo fossa.



14.30.02 COLLEGAMENTI ELETTRICI DELLE PORTE



14.31. Operations to be performed before operating the platform

NOTICE



LUBRICATE ALL GUIDE RAILS USING THE SILICONE SPRAY OIL SUPPLIED WITH THE SYSTEM (F353.05.9017).


LUBRICATE THE SCREW WITH THE SUPPLIED LUBRICATING OIL EP 220 (KIT F352.23.0001).

FILL THE LUBRICATOR WITH THE SUPPLIED LUBRICATING OIL EP 220 (KIT F352.23.0001).

NOTICE



DURING THE FIRST OPERATION, CHECK THAT THE CABLE MOVES CORRECTLY.





14.32. Landing door - adjustments

14.32.01 LANDING DOOR - STOP ADJUSTMENT



Should it be necessary to correct an "door stop mechanical clearance", KIT F353.23.0010 contains the equipment needed to carry out the operation as indicated below.

- ① Open the door leaf
- ② Fix the plates **A** with the self-drilling screws supplied in the kit at the slot in the guide rail.





14.33. Shaft in structure - assembly


14.33.01 IN STRUCTURE SHAFT (WITH SIDE INFILL) - ASSEMBLY

ASSEMBLING THE DOOR


- 2 Position the door **D** accurately in the doorway **E**.
- 3 Mark on the lintel the points **F** where the door is to be anchored using dowels (using the door frame as a template).




- 4 Remove the door **D** and drill the lintel at the anchoring points **F**.





- 5 Reposition the door **D** and anchor it to the lintel with the expansion plugs.





F353.23.0010



- 6 Drill the slab in the slots of the brackets **A** and anchor the door **D** to the slab with the expansion dowels.






F353.23.0010



14.34. Control cabinet



14.34.01 CONTROL CABINET - ASSEMBLY

- Insert the supplied threaded rivets into the holes provided **1**.
- Position and fasten the cabinet with the supplied screws **2**.





14.34.02 CONTROL CABINET - CABLE ROUTING


- Remove cable tray covers **1**.



- From the shaft, insert the cables into the control cabinet through the opening provided **2**.



- Insert flat cables **3** and main wiring **4** into the cable tray.




- After making the necessary connections, secure with cable ties and close the cable tray.

14.34.03 ARMADIO QUADRO ELETTRICO - CHIUSURA FORO MONTANTE




Entrambi i montanti sono preforati per consentire l'installazione dell'armadio quadro elettrico; pertanto i fori di accesso non utilizzati andranno chiusi con tappo in PVC (forniti nel kit) e piastra di chiusura in inox presente negli imballi struttura.

- Inserire nel foro $\varnothing 13$ l'apposito tappo in PVC **1**.
- Chiudere l'apertura con la piastra inox in ed i rivetti in dotazione **2**.



14.34.04 SAFE-PIT - EXTERNAL CONTROL LEVER CONNECTION

- ① Raise the platform so that there is room to operate.
- ② Manually open the safety jack stand.
- ③ Connect an end of the brake cable **A** with sheath to the control lever **B** (located inside the control cabinet on the ground floor **C**)
- ④ Connect the other end of the brake cable **A** with sheath to safety jack stand in the pit **D**.



15. Infills

15.01. Infills - preliminary operations





The infills, the landing doors, and the guide rails (opposite to the mechanics), are installed in a circular sequence from the bottom upwards.
The following will describe the individual operations; it is up to the installer to take the correct reference for the installation of the components.

NOTICE

In outdoor shells, lay the adhesive seal or the silicone on the internal surface of jambs and transoms before installing the infill.

Install the infill on all sides before installing the system.



IMPORTANT!





RISK OF GUIDE RAIL DAMAGING.

The processing debris may damage the guide rails and shoes and cause the machine to malfunction.

Cover/protect the shoes from the processing debris that could seriously damage the guide rails and shoes.

CHECK THE CLEANLINESS OF THE SHOES AT EACH HOLE.



15.02. Infill - silicone application for outdoor use


IMPORTANT!



SEAL ALL THE JOINTS BETWEEN JAMBS AND TRANSOMS AND THE SHELL-ROOF INTERFACE.


In ALL OUTDOOR SHELLS you need to carefully apply silicone for outdoor windows in the locations shown in the figure (in case of both glazed and blanking infill), to avoid possible seepages that would damage the shell.

Use transparent neutral silicone suitable for use in outdoor environments. (non supplied).



15.03. Structure infills - correct positioning

- The following drawings give references for the correct positioning of the infill panels:





IMPORTANT!



RISK OF GLASS DAMAGE.

Do not insert deep threaded u nuts into the guide uprights. Failure to do so may result in glass breakage.






15.04. Infill under the floor door (different from ground floor)



FOR ALL DOORS EXCEPT GROUND FLOOR DOORS

Install the blind infill under the door **BEFORE** installing the landing door.

- Take a standard BLIND infill panel and cut it to size.
- Using the bar as a template, mark the holes, drill them and fasten the infill panel with the rivets provided.



15.05. Structure and mechanics infills - assembling

1.1.01 STRUCTURE INFILLS - PREPARATION AND ASSEMBLY


IMPORTANT!




In outdoor structures, place adhesive sealant or silicone on the inside face of uprights and cross members before fitting the infill.

Mount the infill on all sides before installing the system.

- Pre-mount the cage nuts in the transoms, where the square hole is present **1**.







- Insert the glazing beads following the two steps indicated, at a position corresponding to pre-mounted cage nuts **2A** **2B**.



- Position the glass/panelling using the appropriate suction cups **3**.
- Secure the glazing bead with the screws provided **4**.

21. Additional installations

21.01. Protective canopy (if supplied)




Apply silicone carefully on the three sides of the canopy in order to prevent water seepage.


21.02. Structure - anchoring by ties (optional)

21.02.01 ANCHORING TIES - PREPARATION

- Pre-assemble the ties with the screws provided.



- Mount the anti-vibration feet on the tie as shown in the drawing.



21.02.02 ANCHORING TIES - WALL ANCHORING

IMPORTANT!





Consult the DESIGN DRAWING to check the correct assembly and positioning of clamping fixtures (ties).

- Position the ties against the structure so that the brackets rest against the wall/ceiling.
- Drill the wall at the holes in the brackets **1**.
- Anchor the brackets using the anchor bolts provided **2**.
- If necessary, shim at the rear to achieve correct vertical alignment **3**.



M12x200

S000.23.0019



WARNING



FAILURE TO OBSERVE THE INSTRUCTIONS MAY COMPROMISE STRUCTURE SAFETY.

The anchoring shown here refers exclusively to the installation on a wall/slab of compact, non-cracked concrete (see "ANNEX 1- Anchoring to the shaft by means of plugs (mechanical or chemical)").

17. First test travel

WEAR APPROPRIATE PPE



Before performing the first test travel, make sure that all electrical components are connected correctly.

NOTICE



IT IS RECOMMENDED TO PERFORM A FULL TRAVEL WITH THE SLING IN ADVANCE:

- Thoroughly clean the guide rails and lubricate them with SILICONE-BASED SPRAY OIL (SUPPLIED WITH THE PLATFORM - F353.05.9017).
- Visually check that there are no visible obstacles or protruding materials along the shaft that could interfere with the sling and the basement.
- Check that all STOP devices are disabled.
- Check that the safe pit device is disabled.
- Check that the distance between the carrier and the headroom is the same as that indicated by the design.
- Power the controller by operating it in SERVICE mode.

NOTICE



WITH THE SLING STATIONARY AT THE TOP FLOOR:

- Check that the sling upper travel margin on the guide rails corresponds to design drawing.
- Adjust the position of the limit switch so that it trips after a lifting of approximately 30mm above the floor.
- Lower the platform to the lowest floor.
- Pay close attention to travelling cable proper length and any interference during the travel.
- Adjust the position of the lower limit switch so that it trips after a downward travel of approximately 10 mm below the lowest access.
- Perform a few full travels, checking:
 1. Cable movement.
 2. Any abnormal noise.
 3. That the limit switches do not encounter obstacles.


18. Assembly and completion adjustments of the platform

18.01. Overload - adjustment.


① The overload contact **A** is positioned on the arch, with the corresponding control unit **B**.



For adjustment or maintenance work, always refer to the specific manual supplied with the part.




18. Safety signs to be applied on the platform lift



1

PLATFORM DRIVING FORCE SWITCH



2

PLATFORM ALARM

3

CAUTION! PLATFORM MACHINERY

ENTRANCE FORBIDDEN WITHOUT AUTHORIZATION

4

RECOMMENDED OIL FOR BEARINGS AND GEARS

Synthetic oil ISO VG 220
Viscosity number ≥ 195
Operating temperature: +5°C ... +50°C

5

INSTRUCTIONS FOR EMERGENCY OPERATION

- 1) MAKE SURE ALL THE LANDING DOORS ARE CLOSED;
- 2) MAKE SURE THERE IS NO ONE INSIDE THE CAR; IN CASE THERE ARE PEOPLE INSIDE THE PLATFORM, REASSURE THEM AND WARN THEM TO KEEP CLEAR FROM THE ENTRANCES;
- 3) IDENTIFY PLATFORM POSITION;
- 4) ET "MAINTENANCE MODE" BY TURNING THE CENTRAL SELECTOR (CLOCKWISE);
- 5) PRESS THE "EMERGENCY" BUTTON IN ORDER TO MAKE THE PLATFORM MOVE UP OR DOWN TO THE NEAREST FLOOR;
- 6) LET PEOPLE COME OUT OF THE PLATFORM.

6

7

⚠ DANGER OF CRUSHING!

ACTIVATE THE SAFETY DEVICE THROUGH THE SPECIAL LEVER BEFORE ENTERING INTO THE PIT.

8

EMERGENCY KEY

USE IT TO UNLOCK LANDING DOORS ONLY IN CASE OF EMERGENCY OPERATIONS.

- UNLOCK THE LANDING DOOR
- MAKE SURE THE PLATFORM IS STANDING STILL AT THE FLOOR
- AFTER REDUCING THE LANDING DOOR MAKE SURE THAT IT IS LOCKED

9

⚠ DANGER OF FALLING IN THE PIT

⚠ THE USE OF EMERGENCY KEY IS PROHIBITED TO UNAUTHORIZED PERSONS

WHEN THE EMERGENCY MANOEUVRE HAS BEEN COMPLETED CLOSE AND LOCK ALL LANDING DOORS

8

EMERGENCY KEY

USE IT TO UNLOCK LANDING DOORS ONLY IN CASE OF EMERGENCY OPERATIONS.

9


⚠ DANGER OF FALLING IN THE PIT

⚠ THE USE OF EMERGENCY KEY IS PROHIBITED TO UNAUTHORIZED PERSONS

WHEN THE EMERGENCY MANOEUVRE HAS BEEN COMPLETED CLOSE AND LOCK ALL LANDING DOORS


Apply on landing doors in case of platform installation in public buildings.

10



Apply on landing doors in case of platform out of service.

11



SimpLift® - Cross 50.2 structure and masonry shaft

INSTALLATION AND COMMISSIONING INSTRUCTIONS

⚠ DANGER OF CRUSHING

! ACTIVATE THE OVERHEAD SAFETY DEVICE BEFORE REACHING TO THE ROOF

17 ☐

ON HEAD PROTECTION DEVICE

⚠ WARNING! CRUSHING PLATFORM MACHINERY

! ACTIVATE THE SAFETY DEVICE FROM OUTSIDE THE SHAFT BEFORE ENTERING INTO THE PIT

16 ☐

⚠ WARNING! CRUSHING

! BEFORE LEAN OUT OF THE ROOM LIFT

- PLACE MECHANICAL DEVICE FOR THE END PLATE DEFENCE AND ENABLE IT FROM THE CAR
- LEAN OUT OF THE ROOF ONLY WHEN THE ACOUSTIC SIGNAL IS OFF

15 ☐

⚠ WARNING! CRUSHING PLATFORM MACHINERY

🚫 ENTRANCE FORBIDDEN WITHOUT AUTHORIZATION

14 ☐

! RISK OF DAMAGE TO THE SYSTEM

PLATFORM MAIN SWITCH

CUT OFF THE POWER SUPPLY ONLY WHEN THE PLATFORM HAS REACHED THE FURTHER DOWN FLOOR


13 ☐


⚠ DANGER OF CRUSHING!

STOP SWITCH

- ACTIVATE THE SWITCH WHEN ENTERING THE PIT
- RELEASE THE SWITCH WHEN GOING OUT OF THE PIT

12 ☐





On the car roof



26



27



18



FILL IN THE
NUMBER PLATE




19

IMPORTANT!



Check the presence
of the rating plate
supplied with the
hand control.




24



25

Attach it to the inside of the manual
landing doors on the lock side.



20. Final checks and adjustments

IMPORTANT!



Perform the checks and adjustments described in the manual IM.TEC.126 "FINAL CHECKS" in order to be able to consider system installation as completed.

21. Platform noise



The sources of platform noise are the motor, the brake, and the shoes that slide on the guide rails, particularly during full load lifting (including maximum permissible overload).

The motor is located at the rear of the sling between the guide rails and behind the protective casing.

User position is located on the carrier, so the user is not directly subject to noise emissions from noise disturbance sources. Despite this assumption, as precautionary measure, measurements were taken directly around the above sources, in an industrial environment without other machines in operation.

In the various configurations examined, all measurements resulted in sound pressure levels below the value of 70dB(A).



IMPORTANT INFORMATION

ANNEX 1
Anchoring to the shaft by means of plugs (mechanical or chemical)

SHAFT IN REINFORCED CONCRETE

Unless otherwise noted, all plugs are M10 in size and require a hole in the wall with 10 mm bit.


h₁	=	Hole minimum depth
L_t	=	Plug length
d₀	=	Hole diameter
t_{fix}	=	Fixable shim
t_{inst}	=	Tightening torque
Ch	=	Wrench
h_{ef}	=	Anchoring depth



Carefully clean the hole before installation.

SHAFT IN LOAD-BEARING MASONRY

CAUTION




The anchoring of the jambs in shaft in masonry (**realized with elements suitable for the construction of load-bearing/ structural masonry***), requires a reduction of the bracket pitch in order to cope with the lower mechanical strength of the shaft wall.

* Building materials suitable for the realization of load-bearing walls also in seismic areas, calculated and realized in compliance with the law in force in the field in the installation sites
(IT) - D.M. January 17, 2018 (Building technical standards 2018).


The bracket pitches are 1250 mm, starting from the pit bottom = 500 mm.

NOTICE




Always refer to the design drawing for installation.

CAUTION



For all the cases not covered by the described types, a site survey and a project by a qualified technician is necessary.



ANCHORING in LOAD-BEARING MASONRY SHAFT WITH SOLID, COMPACT ELEMENTS


For the application of chemical anchors on load-bearing masonry with solid, compact elements, a special kit has been developed (code F350.23.0026V01), consisting of:

- 16 x galvanized THREADED RODS M10x130 with 45° cut (anti-rotation);
- 2 x CARTRIDGES (300 ml each) of injection anchor*, usable with normal silicone guns;
- 2 x Universal MIXERS ø9 mm in addition to the 4 supplied with the cartridges.

* Applicable for solid and hollow elements in cement, natural stone.

Each kit is suitable for the installation of 8 guide rail fixing brackets, which correspond on average to one stop. Therefore, by way of example, for a 3-stop system, 3 F350.23.0026V01 KITS will be required, with the positioning of the brackets according to the example drawing.


h₁	=	Hole minimum depth
L_b	=	Bar length
L_t	=	Plug length
d₀	=	Hole nominal diameter
ø_b	=	Bar diameter
T_{fix}	=	Fixable shim



Calculation of the bar length:

$$L_b = L_t + T_{fix}$$

INSTALLATION SEQUENCE:



Carefully clean the hole before installation.

IMPORTANT INFORMATION

ANCHORAGE in a LOAD-BEARING MASONRY SHAFT WITH HOLLOW ELEMENTS

The special kit F350.23.0025V01 for chemical bolts application is composed of:


- n° 16 zinc plated THREADED RODS 45° cut (anti rotation) (M10x130 GALVANISHED CHEMSET STUD);
- n° 2 pcs 300 ml CARTRIDGES of ANCHORING ADHESIVE*, to be used with standard caulking guns (skeleton gun);
- n° 2 multipurpose MIXERS ø9 mm, additionally to the 4 mixers foreseen for the cartridges;
- n° 2 FINE METAL MESH SLEEVE ø16 mm, length 1 mt each.

* Valido per elementi in: calcestruzzo, pietra naturale, mattone pieno e semipieno.

Each kit is sufficient for 8 brackets, required for approx. 1 stop.

For instance, 3 F350.23.0025V01 kits are required for a 3 stops' lift, the brackets being positioned as per the sample drawing.


h₁	=	Minimum hole depth
L_b	=	Rods length
L_t	=	Dowel length
d₀	=	Hole diameter
d_b	=	Metal Mesh Sleeve diameter
ø_b	=	Rods diameter
T_{fix}		Fixable thickness



Threaded rods length calculation:

$$L_b = L_t + T_{fix}$$

ASSEMBLY SEQUENCE



Carefully clean the hole before installation.



Via Caduti del Lavoro, 16/22

43058 Sorbolo Mezzani (PR)

Tel. +39 0521 695311

info@arealifting.com

www.arealifting.com

MADE IN ITALY

